

7. AUXILIARY EQUIPMENT:

- a) Upper kelly cock valve with handle available.
- b) Lower kelly cock valve with handle available.
- c) Safety valves and subs to fit all drill string connections in use.
- d) Inside BOP or float sub available.
- e) Wear ring in casing head
- f) No floats at bit
- g) Monitoring of mud system will be electronic/mechanical below 9,500'.

8. Testing Logging and Coring Program:

Drill Stem Tests will be made when samples, drilling time and other data indicate a test is warranted.

It is planned that electric logs will include Gamma Ray-CNL, FDC logs and dual laterologs.

Note: A gamma ray log will be run over the surface casing from its base to the ground surface.


No coring is planned.

9. Anticipated abnormal pressure in Atoka and Morrow $BHP \approx 8000 \text{ psi (max)}$

10. Anticipated Starting Date:

It is planned to commence drilling operations on or before February 15, 1998 to last a period of 85 days.

Contact L. G. JOHNSON at 915-682-3753
With any questions concerning the Drilling Plan.


L. G. JOHNSON
Drilling Superintendent