

Operator Name: Conoco
 Well Name: SEMU Burger #141
 Job Description: 8-5/8" Surface
 Date: December 2, 1999



Proposal No: 160252710A

WELL DATA

ANNULAR GEOMETRY

ANNULAR I.D. (in)	DEPTH(ft)	
	MEASURED	TRUE VERTICAL
12.250 HOLE	1,500	1,500

SUSPENDED PIPES

DIAMETER (in)		WEIGHT (lbs/ft)	DEPTH(ft)	
O.D.	I.D.		MEASURED	TRUE VERTICAL
8.625	8.097	24	1,500	1,500

Float Collar set @ 1,460 ft
 Mud Density 9.00 ppg
 Est. Static Temp. 86 ° F
 Est. Circ. Temp. 85 ° F

VOLUME CALCULATIONS

1,200 ft	x	0.4127 cf/ft	with	99 % excess	=	984.9 cf
300 ft	x	0.4127 cf/ft	with	106 % excess	=	254.6 cf
40 ft	x	0.3576 cf/ft	with	0 % excess	=	14.3 cf (inside pipe)
TOTAL SLURRY VOLUME					=	1253.9 cf
					=	224 bbls