

Operator Name: Conoco
 Well Name: SEMU Burger #141
 Job Description: 5-1/2" Long String
 Date: December 2, 1999



Proposal No: 1602/2710A

WELL DATA

ANNULAR GEOMETRY

ANNULAR I.D. (in)	DEPTH(ft)	
	MEASURED	TRUE VERTICAL
8.097 CASING	1,500	1,500
7.875 HOLE	4,300	4,300

SUSPENDED PIPES

DIAMETER (in)		WEIGHT (lbs/ft)	DEPTH(ft)	
O.D.	I.D.		MEASURED	TRUE VERTICAL
5.500	4.950	15.5	4,300	4,300

Float Collar set @ 4,260 ft
 Mud Density 8.70 ppg
 Est. Static Temp. 106 ° F
 Est. Circ. Temp. 99 ° F

VOLUME CALCULATIONS

1,500 ft	x	0.1926 cf/ft	with	0 % excess	=	288.9 cf
1,000 ft	x	0.1733 cf/ft	with	54 % excess	=	266.1 cf
1,800 ft	x	0.1733 cf/ft	with	49 % excess	=	465.0 cf
40 ft	x	0.1336 cf/ft	with	0 % excess	=	5.3 cf (inside pipe)
TOTAL SLURRY VOLUME					=	1025.4 cf
					=	183 bbls