

7" 29# AND 32# S-95 AND S-105 LT&C CASING TO BE SET AT 12,500' IN 8-3/4" HOLE. CASING TO BE CEMENTED WITH 1650 SACKS OF 50/50 POZ H. CEMENT TO TIE BACK.

4-1/2" 13.5# S-95 AND S-105 LINER TO BE SET IN THE INTERVAL 12,300' TO TD IN 6" HOLE. LINER TO BE CEMENTED WITH 300 SACKS OF CLASS "H". CEMENT TO CIRCULATE LINER.