Blowout Prevention Program- Attachment to Form C-101

0-1350'	20" 2000# annular preventer system.
1350'-5750'	13-5/8" 3000# double ram type preventers and a 3000# annular preventer. A choke manifold and 120 gallon accumulator with floor and remote operating stations and auxiliary power system. Test BOP to 1000 psi.
5750'-11,800'	11" 10,000# triple ram type preventers, 5000# annular preventer and rotating head body. Test BOP to 3000 psi. Install hydraulic drilling choke and mud/gas separator prior to 11,000'.
11,800'-13,100'	11" 10,000# triple ram type preventers, 5000# annular preventer and rotating head body. Test all rams, choke manifold,kill line, upper and lower kelly valves to 10,000 psi. Test annular BOP to 3000 psi.

Any equipment failing to test satisfactorily, will be repaired or replaced. Results of the BOP test will be recorded in the Driller's Log.

The BOP's will be maintained ready for use until drilling operations are completed. BOP drills will be conducted as necessary to assure that equipment is operational and each crew is properly trained to carry out emergency duties.

Accumulator shall maintain a pressure capacity reserve at all times to provide for the close-open-close sequence of the blind and pipe rams of the hydraulic preventers.