

South Eunice Unit No. 33

Page 2

test squeeze to 1000 psi for 15 mins. Drill out cal-seal plug at 3635' and clean well out to 3813' P.O.H.
G.I.H w/ 2.812" SN, 4; to 2 1/16" tbg, crossover & 2 7/8" tbg.
Land tbg in 5' seal line extension at 3625'.

8. Acidize 3644'-3810' w/ 90 bbls 15% HCL-FC acid w/ 60 gals Checker-Sol or equivalent inhibited for 24 hrs at 100° F. Pump 600# graded rock salt mixed in 5 bbls gelled 9" brine in 3 equal stages. Flush w/ 30 bbls 9" brine. Swab well. P.O.H.

9. G.I.H w/ 3.00" anchor seal assembly & 2 3/8" plastic-coated tbg. Load backside w/ mixture of 8 gals Conoco No. 1 pke fluid plus 4 gals Conoco No. 2 pke fluid mixed in 80 bbls 2% KCL TFW. Latch tbg into pke at 3530'.

10. Return well to injection. Do not exceed 500 psi surface pressure. Let well stabilize for 1 week. Run injection profile survey.

For further information contact Mr. [Name] at 397-5866