

B. A. Christmas No. 1

Tubb pool

9. Sand Frac dwn. 2 7/8" Tbg. w/ 52,000 gal. gelled water, 48,000 # 20/40 sd., 24,000 # 12/20 sd. Displace dwn. Tbg. w/ 2% KCL water. Space sand in 6 stages using 7/8" RCNB as sealers between stages.
10. Release pressure from Tbg. Reverse excess sd. from csg. to RBP. Rel. RBP & POOH w/ 2 7/8" Tbg. SN & Pkr. Lay dwn. rent string in singles.
11. Run packer on 2 3/8" Tbg. to 6050'. Set pkr. & press. annules to 500#. Swab well & clean up. Test into frac. tank.
12. Return well to producing status.

RECEIVED
OCT 6 1986
OFFICE
HOBBS