

Adobe State #3 – Proposed P&A Wellbore

0'-349' 8 5/8" OD SURFACE CASING - CEMENTED WITH 200 SX. CIRCULATED

CASING LEAK @ 700'

RBP @ 3010'

PERFS: 3506-34

0'-3786' 4 1/2" OD PRODUCTION CASING - CEMENTED WITH 250 SX. TOC @ 2790' BY TEMP

TD= 3800
KB ELEV= 3411'