

A. H. BLINEBRY WELL NO. 4

Total Depth 8377'

13-3/8" casing cemented at 274' with 300 sacks.

9-5/8" casing cemented at 2633' with 1650 sacks.

Hole will be filled to total depth with heavy drilling mud and following cements plugs will be spotted as follows: 10 sacks, 7550-7600' (to shut off porous section at 7460 - 7580' and also seal off lower portion of hole). 12 sacks, 7150 - 7210' (6-1/4" hole). 20 sacks, 6940 - 7000' (8-3/4" hole). 20 sacks, 6520 - 6580'. 20 sacks, 6180 - 6270'. 20 sacks, 5490 - 5550'. 20 sacks, 5240-5300'. 20 sacks 4820 - 4880'. 20 sacks, 4250 - 4310'. 20 sacks, 2680 - 2740' (base of salt). 14 sacks 1420 - 1450' (top of salt section in 9-5/8" casing. All 13-3/8" and 9-5/8" casing will be left cemented in the hole, and the customary 4" pipe marker will be cemented in the top of the hole with approximately 20 sacks of cement. All mud and cement will be pumped in through drill pipe.

The above confirms telephone conversation and approval by your office as of June 14, 1946.

