

BELL LAKE UNIT No. 17

0'-21' AGL

RECOMMENDED PROCEDURE

RECOMPLETE IN BONE SPRINGS LIME.

- 1) RIG-UP AND KILL WELL WITH 10 LB BRINE, IF NECESSARY.
- 2) PULL TUBING AND SET A CEMENT RETAINER @ 9150'
- 3) PUMP THRU RETAINER 200 SX CLASS 'H' CEMENT MIXED 16.4 PPG + 1.06 ft^3/SX . SPOT 50' ft CLASS 'H' CEMENT ON TOP OF RETAINER. (RETARD CEMENT FOR 2 HR. Min Pumping Time)
- 4) SPOT 200 GAL 15% NE-HCL, INHIBITED FOR 24 Hrs @ 130°F, FROM 8850' to 8743'
- 5) PERFORATE WITH A 4" CENTRALIZED CASING GUN @ 8769' to 8775', 8778' to 8783', & 8801' to 8809 W/2 JS PF.
- 6) RUN TUBING WITH PACKER AND SET @ $\pm 8730'$
- 7) SWAB TEST AND REPORT RESULTS TO HOBBS OFFICE.

RAF

10-24-78

RECOMPLETE BONE SPRINGS LIME.