

BACK BASIN UNIT WELL NO. 1

CASING

<u>SIZE</u>	<u>GRADE</u>	<u>WEIGHT</u>	<u>CONDITION</u>
20"	K-55	133#	New
13 3/8"	S-80	68&61#	New
9 5/8"	S-95/N-80	53.5&47#	New
If warranted:			
5"	C-75	23.2#	New

Testing Procedures and Testing Frequency for Pressure Control Equipment

Test surface equipment initially.

Test surface equipment after setting surface and intermediate casing.

Anticipated Testing, Logging & Coring Program

Drill stem testing is anticipated in the Delaware, Bone Springs, Atoka, and Morrow.

Logs will be BHC Sonic, Dual Laterolog-DIL CNL-FDC.

No cores will be cut.