

EXHIBIT "A"

STRATA PRODUCTION CO.

ARACANGA FEDERAL #2
SECTION 9 T23S-R31E
LEA COUNTY, N.M.

NM-62224
SPUD DATE 8/22/92

13 3/8"-48#/FT. H-40
SET @ 380'
350 SX CLASS "C" W/ 2% CACL
CIRC. 100 SX

PLUGGING PROCEDURE

1. SET CIBP @ 6300' AND SPOT 35' OF CEMENT ON TOP OF CIBP.
2. SET 100' CEMENT PLUG @ 4500' - 4600'. 1305 CU.FT./FT., 15 SX
3. CUT CASING AT FREEPOINT, +/- 3000', PULL AND LAY DOWN.
4. SET 100' CEMENT PLUG 1/2 IN AND 1/2 OUT OF CASING STUB, 25 SX.
5. SET 100' PLUG 1/2 IN AND 1/2 OUT OF THE SURFACE CASING SHOE, 330' - 430', 3422 CU.FT./FT., 35 SX.
6. SET 50' SURFACE PLUG @ 50' - 0'. 20 SX
7. INSTALL DRY HOLE MARKER AND CLEAN LOCATION.

CIRCULATE THE HOLE WITH PLUGGING MUD, MINIMUM SPECIFICATIONS, 9.0 LB./W/ 25 SX GEL PER 1000 BBLs., VIS. +/- 35.

CALCULATED T.O.C. @ 3500'

8 5/8"-32 & 24 #/FT J-55
SET @ 4555'
110 "7" SX "HLC & 200 SX CLASS "C" W/ 2% CACL
CIRC. 150 SX

D.V. TOOL @ 5967

6331-6338, 16 HOLES

T.O.C. @ 6661'

LOST RETURNS AT 6975'

7189-7194, 12 HOLES
7232-54 DRILLING BREAK
EZ-DRILL @ 7455'

7436-7468, 19 HOLES
SQUEEZED 7460-68, CIRC. TO THE UPPER PERFS.

CIBP @ 8450' W/ 30' CEMENT
8477-8481, 8 HOLES
8520-8546, 14 HOLES
8602-8635, 15 HOLES

CIBP @ 8590' W/ 35' CEMENT

5 1/2"-17#/FT. @ 8976'
1ST STAGE 700 SX 50/50 POZ
2ND STAGE 520 SX 50/50 POZ

RECEIVED
NOV 3 10 05 AM '95