

(B) Open hole logs may or not be run - A cased hole GR-Neutron will be run.

(C) No conventional coring is anticipated.

(D) Further testing procedures will be determined after the 5 1/2" production casing has been cemented at TD based on drill shows, and log evaluation, and drill stem test results.

9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:

No abnormal pressures or temperatures are anticipated. The estimated bottom-hole temperature (BHT) at TD is 100 degrees F and estimated maximum bottom-hole pressure (BHP) is 800 psig.

10. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is JUNE 3, 1997. Once commenced, the drilling operation should be finished in approximately 7 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.