

8. TESTING, LOGGING AND CORING PROGRAM:

Samples: Samples will be caught at regular intervals

DST: Drill stem tests will be made when samples, drilling time or other data indicate a test is warranted.

Logging: Logs will include CNL-GR, FDC and DLL.

Coring: None planned

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE:

None anticipated

10. ANTICIPATED STARTING DATE: Work will commence as soon as the Application is approved and will continue for about 30 days.