

Scientific Drilling Inc.

Planning Report



Company: Texaco E & P, Inc. **Date:** 05/03/2000 **Time:** 11:19:51 **Page:** 1
Field: Teague (Drinkard) **Co-ordinate(NE) Reference:** Site: Lea County, Texas, Grid North
Site: Lea County, Texas **Vertical (TVD) Reference:** SITE 0.0 above Mean Sea Level
Well: B. F. Harrison "B" #6 **Section (VS) Reference:** Site (0.0E,0.0N,270.0Azi)
Wellpath: OH Original hole **Plan:** Plan #1

Field: Teague (Drinkard)

Map System: US State Plane Coordinate System 1927
Ellipsoid: Clarke - 1866
Sys Datum: Mean Sea Level

Map Zone: Texas, Central Zone
North Reference: Grid
Geomagnetic Model: igrf2000

Site: Lea County, Texas

Site Position: Northing: ft Latitude:
From: Local Only Easting: ft Longitude:
Position Uncertainty: 0.0 ft Magnetic Declination: 0.00 deg
Water Depth: 0.0 ft Grid Convergence: deg

Well: B. F. Harrison "B" #6

Well Position: +N/-S 0.0 ft Northing: ft Latitude:
From Slot: +E/-W 0.0 ft Easting: ft Longitude:
Position Uncertainty: 0.0 ft

Wellpath: OH Original hole

Vertical Section: +N/-S 0.0 ft **Drilled From:** Surface
From: Site +E/-W 0.0 ft **Tie-on Depth:** ft
Measured Depth Reference: SITE 0.0 ft **V.Section Direction:** 270.00 deg
Above System Datum: Mean Sea Level

Plan: Plan #1

Date Composed: 05/03/2000
Version: 1

Principal: Yes

Locked: No

Plan Section Information

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target
6000.0	0.00	270.00	6000.0	0.0	0.0	0.00	0.00	0.00	0.00	
6320.0	0.00	270.00	6320.0	0.0	0.0	0.00	0.00	0.00	270.00	
6410.7	63.50	270.00	6393.3	0.0	-45.3	70.00	70.00	0.00	270.00	
6414.7	63.63	270.17	6395.0	0.0	-48.9	5.00	3.19	4.30	50.32	
7889.3	63.63	270.17	7050.0	4.0	-1370.0	0.00	0.00	0.00	0.00	Toe #6

Section 1 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
6000.0	0.00	270.00	6000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
6100.0	0.00	270.00	6100.0	0.0	0.0	0.0	0.00	0.00	0.00	270.00
6200.0	0.00	270.00	6200.0	0.0	0.0	0.0	0.00	0.00	0.00	270.00
6300.0	0.00	270.00	6300.0	0.0	0.0	0.0	0.00	0.00	0.00	270.00
6320.0	0.00	270.00	6320.0	0.0	0.0	0.0	0.00	0.00	0.00	270.00

Section 2 : Start Build 70.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
6325.0	3.50	270.00	6325.0	0.0	-0.2	0.2	70.00	70.00	0.00	0.00
6330.0	7.00	270.00	6330.0	0.0	-0.6	0.6	70.00	70.00	0.00	0.00
6335.0	10.50	270.00	6334.9	0.0	-1.4	1.4	70.00	70.00	0.00	0.00
6340.0	14.00	270.00	6339.8	0.0	-2.4	2.4	70.00	70.00	0.00	0.00
6345.0	17.50	270.00	6344.6	0.0	-3.8	3.8	70.00	70.00	0.00	0.00
6350.0	21.00	270.00	6349.3	0.0	-5.4	5.4	70.00	70.00	0.00	0.00
6355.0	24.50	270.00	6353.9	0.0	-7.4	7.4	70.00	70.00	0.00	0.00
6360.0	28.00	270.00	6358.4	0.0	-9.6	9.6	70.00	70.00	0.00	0.00
6365.0	31.50	270.00	6362.8	0.0	-12.1	12.1	70.00	70.00	0.00	0.00
6370.0	35.00	270.00	6366.9	0.0	-14.8	14.8	70.00	70.00	0.00	0.00
6375.0	38.50	270.00	6371.0	0.0	-17.8	17.8	70.00	70.00	0.00	0.00
6380.0	42.00	270.00	6374.8	0.0	-21.0	21.0	70.00	70.00	0.00	0.00