

7. Abnormal Conditions, Bottom hole pressure and potential hazards:

Anticipated BHP:

From: 0	TO: 700	Anticipated Max. BHP: 200	PSI
From: 700	TO: 4275	Anticipated Max. BHP: 1200	PSI
From: 4275	TO: 10,000	Anticipated Max. BHP: 3400	PSI

Abnormal Pressures Anticipated: None

Lost Circulation zones anticipated: None

H2S Zones Anticipated: None

Maximum Bottom Hole Temperature: 140 F

8. ANTICIPATED STARTING DATE:

Plans are to drill this well as soon as possible after receiving approval. It should take approximately 15 days to drill the well with completion taking another 20 days.