

6. Source of Construction Materials:

Caliche needed for the road and well pad will be taken from the proposed reserve pit. An alternate plan will be to obtain caliche from a borrow pit located within the 400' x 400' archaeologically cleared tract at the proposed well site. If sufficient quality or quantity of caliche is not available, it will be transported to the proposed road and well site from an existing BLM approved caliche pit. The BLM will be notified and consulted if caliche must be obtained off location.

7. Method of Handling Waste Disposal:

- a) Drill cuttings will be disposed into the reserve pit.
- b) Drilling fluids will be contained in the reserve pit. The reserve pit will be an earthen pit, approximately 150' x 150' x 6' deep and fenced on three sides prior to drilling. The fourth side will be fenced immediately following rig removal. The reserve pit will be lined with plastic (5-7 mil thickness) to minimize loss of drilling fluids.
- c) Water produced from the well during completion may be disposed into the reserve pit or a steel tank (depending upon rates).
- d) Drilling fluids will be allowed to evaporate in the drilling pits until the pits are dry.
- e) Oil produced during testing will be stored in steel test tanks until sold.
- f) Trash, waste paper, garbage, and junk will be placed in a trash bin located on the drill site pad. It will be transported to an approved landfill for disposal within 30 days after completion of drilling and/or completion of operations. All waste material will be contained to prevent scattering by the wind.
- g) A portable chemical toilet will be provided on the location for human waste during the drilling and completion operations.

8. Ancillary Facilities:

No other facilities will be built as a result of the operations on this well.

RECEIVED
Hobbs
JUN 10 1960