

Submit to Appropriate
District Office
State Lease - 6 copies
Fee Lease - 5 copies

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-101
Revised 1-1-89

OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, New Mexico 87504-2088

DISTRICT I
P.O. Box 1980, Hobbs, NM 88240

DISTRICT II
P.O. Drawer DD, Artesia, NM 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

API NO. (assigned by OCD on New Wells)
30-025-31972
5. Indicate Type of Lease STATE ☒ FEE ☐
6. State Oil & Gas Lease No. B-9613

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work: DRILL ☒ RE-ENTER ☐ DEEPEN ☐ PLUG BACK ☐		7. Lease Name or Unit Agreement Name WEST DOLLARHIDE DRINKARD UNIT	
b. Type of Well: OIL WELL ☒ GAS WELL ☐ OTHER ☐ SINGLE ZONE ☒ MULTIPLE ZONE ☐		8. Well No. 125	
2. Name of Operator TEXACO EXPLORATION AND PRODUCTION INC.		9. Pool name or Wildcat DOLLARHIDE TUBB DRINKARD	
3. Address of Operator P. O. Box 3109, Midland, Texas 79702			
4. Well Location Unit Letter N : 1150 Feet From The SOUTH Line and 1400 Feet From The WEST Line Section 33 Township 24-SOUTH Range 38-EAST NMPM LEA County			
10. Proposed Depth 7565'		11. Formation DRINKARD	
12. Rotary or C.T. ROTARY			
13. Elevations (Show whether DF, RT, GR, etc.) GR-3169'		14. Kind & Status Plug. Bond BLANKET	
15. Drilling Contractor TO BE SELECTED		16. Approx. Date Work will start JUNE 1, 1993	

17. PROPOSED CASING AND CEMENT PROGRAM					
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
20	16	65#	40'	REDI-MIX	SURFACE
14 3/4	11 3/4	42#	1175'	700	SURFACE
11 (OPTIONAL)	8 5/8	32#	4200'	1350	SURFACE
7 7/8	5 1/2	15.5# & 17#	7565'	900	3000'

CEMENTING PROGRAM: CONDUCTOR - REDIMIX.

SURFACE CASING - 500 SX CLASS C w/ 4% GEL & 2% CaCl₂ (13.5ppg, 1.74cf/s, 9.1gw/s). F/B 200 SX CLASS C w/ 2% CaCl₂ (14.8ppg, 1.32cf/s, 6.3gw/s).

INTERMEDIATE CASING - 950 SX 35/65 POZ CLASS H w/ 6% GEL, 5% SALT & 1/4# FLOCELE (12.8ppg, 1.94cf/s, 10.4gw/s). F/B 400 SX CLASS H w/ 2% CaCl₂ (15.6ppg, 1.19cf/s, 5.2gw/s).

PRODUCTION CASING - 400 SX 35/65 POZ CLASS H w/ 6% GEL, 5% SALT & 1/4# FLOCELE (12.8ppg, 1.94cf/s, 10.4gw/s). F/B 500 SX CLASS H (15.6ppg, 1.18cf/s, 5.2gw/s).

INTERMEDIATE CASING WILL NOT BE SET IF NO WATER FLOW IS ENCOUNTERED AND PRODUCTION CEMENT WILL BE ADJUSTED.

CHEVRON OPERATES A WELL IN THIS QUARTER QUARTER SECTION AND HAS BEEN FURNISHED A COPY OF THIS APPLICATION.

UNORTHODOX LOCATION - EXCEPTION HAS BEEN REQUESTED (COPY ATTACHED).

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW PRODUCTIVE ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE C.P. Basham / c.w.h. TITLE DRILLING OPERATIONS MANAGER DATE 05-10-93

TYPE OR PRINT NAME C. P. BASHAM

TELEPHONE NO. (915) 688-4620

(This space for State Use)

ORIGINAL SENT TO DISTRICT OFFICE
DISTRICT OFFICE

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

1151-3205

JUN - 4 1993

Permit Expires 6 Months From Approval
Date Unless Drilling Underway.

Submit to Appropriate
District Office
State Lease - 4 copies
Fee Lease - 3 copies

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised 1-1-89

OIL CONSERVATION DIVISION

P.O. Box 2088
Santa Fe, New Mexico 87504-2088

DISTRICT I
P.O. Box 1980, Hobbs, NM 88240

DISTRICT II
P.O. Drawer DD, Artesia, NM 88210


DISTRICT III
1000 Rio Arriba Rd., Aztec, NM 87410

WELL LOCATION AND ACREAGE DEDICATION PLAT

All Distances must be from the outer boundaries of the section

Operator TEXACO EXPLORATION AND PRODUCTION INC			Lease WEST DOLLARHIDE DRINKARD UNIT		Well No. #125
Unit Letter N	Section 33	Township 24 SOUTH	Range 38 EAST	County NMPM LEA	
Actual Footage Location of Well: 1150 feet from the SOUTH line and 1400 feet from the WEST line					
Ground level Elev. 3169'	Producing Formation TUBB DRINKARD (ABO) AND (DRINKARD)			Dedicated Acreage: 40 Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or Indian ink on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interest of all owners been consolidated by communitization, unitization, force-pooling, etc.?
☐ Yes ☐ No If answer is "yes" type of consolidation _____
If answer is "no" list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary).
No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, force-pooling, or otherwise) or until a non-standard unit, eliminating each interest, has been approved by the Division.



OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Signature

R. D. Mariott

Printed Name

R. D. MARIOTT

Position

DIVISION SURVEYOR

Company TEXACO EXPLORATION
& PRODUCTION INC

Date

MAY 5, 1993

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

MAY 5, 1993

Date Surveyed

Signature & Seal of
Professional Surveyor



Paul D. Harrison

Certificate No.

4882

**DRILLING CONTROL
CONDITION II-B 3000 WP
FOR AIR DRILLING OR
WHERE NITROGEN OR AIR BLOWS ARE EXPECTED**

H₂S TRIM REQUIRED
YES _____ NO _____



DRILLING CONTROL

MATERIAL LIST - CONDITION II - B

- | | |
|----------------|--|
| A | Texaco Wellhead |
| B | 3000# W.P. drilling spool with a 2" minimum flanged outlet for kill line and 3" minimum flanged outlet for choke line. |
| C | 3000# W.P. Dual ram type preventer, hydraulic operated with 1" steel, 3000# W.P. control lines (where substructure height is adequate, 2 - 3000# W.P. single ram type preventers may be utilized). |
| D | Rotating Head with fill up outlet and extended Bloode Line. |
| 1,3,4,
7,8, | 2" minimum 3000# W.P. flanged full opening steel gate valve, or Halliburton Lo Torc Plug valve. |
| 2 | 2" minimum 3000# W.P. back pressure valve. |
| 5,6,9 | 3" minimum 3000# W.P. flanged full opening steel gate valve, or Halliburton Lo Torc Plug valve. |
| 12 | 3" minimum schedule 80, Grade "B", seamless line pipe. |
| 13 | 2" minimum x 3" minimum 3000# W.P. flanged cross. |
| 10,11 | 2" minimum 3000# W.P. adjustable choke bodies. |
| 14 | Cameron Mud Gauge or equivalent (location optional in choke line). |
| 15 | 2" minimum 3000# W.P. flanged or threaded full opening steel gate valve, or Halliburton Lo Torc Plug valve. |



TEXACO, INC.
MIDLAND DIVISION
MIDLAND, TEXAS



SCALE	DATE	EST. NO.	DRG. NO.
DRAWN BY			
CHECKED BY			
APPROVED BY			

EXHIBIT C



Texaco USA
Producing Department
Midland Division

PO Box 3109
Midland TX 79702-3109

May 10, 1993

GOV - STATE AND LOCAL GOVERNMENTS

Unorthodox Locations

West Dollarhide Drinkard Unit

Well Nos. 123, 125, 126, 127, 128

Lea County, New Mexico

State of New Mexico

Energy and Minerals Department

Oil Conservation Division

P. O. Box 2088

Santa Fe, New Mexico 87501-2088

Attention: Mr. Michael E. Stogner

Gentlemen:

An exception, by administrative approval, to Rule 104 F.I. is requested for Texaco Exploration and Production Inc.'s West Dollarhide Drinkard Unit Well Nos. 123, 125, 126, 127, and 128. The wells are located as follows:

Well No. 123:	1275' FSL & 200' FWL,	Sec.32, T-24-S, R-38-E
Well No. 125:	1150' FSL & 1400' FWL,	Sec.33, T-24-S, R-38-E
Well No. 126:	2450' FSL & 150' FWL,	Sec.33, T-24-S, R-38-E
Well No. 127:	2630' FNL & 1440' FWL,	Sec.33, T-24-S, R-38-E
Well No. 128:	1310' FNL & 150' FWL,	Sec.33, T-24-S, R-38-E

The wells must be drilled in these locations to ensure proper development on 10-acre spacing. Wells drilled previously on 10-acre spacing have proven to be viable wells. These wells will be completed in the Drinkard formation.

It should be noted that there are no affected offset operators to Well Nos. 123, 125, 126, 127, or 128.

Attached are Forms C-102 for each well and a lease plat showing the existing wells, and locations of the subject wells.

Yours very truly,

C.P. Basham /cwh

C. P. Basham
Drilling Operations Manager


CWH:cwh

cc: NMOCD, P. O. Box 1980, Hobbs, NM 88240


R 38 E

T 24 S

T 25 S



○ PROPOSED LOCATION



TEXACO E & P INC.		
MIDLAND	TEXAS	U.S.A.
WEST DOLLARHIDE DRINKARD UNIT		
LEA COUNTY, NEW MEXICO		
BASE MAP		
TUBB/DRINKARD/ABO WELLS ONLY		
J. F. C. 1955 75-100-00		