

Multi Point Surface Use and Operations Plan
OXY USA Inc.'s Myers Langlie Mattix Unit #134

Page 2

4. Location of Existing and/or Proposed Facilities

An injection line hooking the well up to the waterflood injection station is already in place and will be utilized. All permanent above ground facilities will be painted in accordance with the BLM's painting guidelines simulating the color of sandstone brown.

5. Location and Type of Water Supply

Fresh water will be used to Re-Enter this well. It will be purchased near Jal, New Mexico and transported to the well site.

6. Source of Construction Materials

The location was never reclaimed after the well was P&A'd.

7. Method of Handling Waste Disposal

- A. Drill Cuttings will be disposed of in workover pit.
- B. Drilling fluids will be disposed in the reverse unit steel pits.
- C. Water produced during tests will be disposed of in the workover pit.
- D. Current laws and regulations pertaining to the disposal of human waste will be complied with.
- E. Trash, waste paper, garbage and junk will be placed in steel bins and hauled off location and disposed of in a proper manner.

8. Ancillary Facilities

- A. None needed.