

Application for Permit to Re-Enter
Myers Langlie Mattix Unit #134

Page 2

6. Total depth is 3,726 feet.

7. Tops of important geologic markers.

Salt	1200'
"	2820'
Yates	3001'
Seven Rivers	3227'
Queen	3504'

Total Depth	3726'
-------------	-------

8. Estimated depths at which anticipated water, oil, gas or other mineral bearing formations are expected to be encountered:

Primary Objective:	Queen	3504'
--------------------	-------	-------

9. The original casing program is as follows:

Surface: 8-5/8" OD 22.7# casing

Production: 4-1/2" OD 9.5# casing

10. Casing setting depth and cementing program:

A. 8-5/8" OD surface casing set at 351' in 12-1/4" hole. Cemented with 250 sacks, circulated 15 sacks to pit.

B. 4-1/2" OD production casing set @ 3725' in 7-7/8" hole. Cemented with 300 sacks, calculated TOC @ 2700'.

11. Pressure Control Equipment

0' - 3691'	10" 3000# ram type preventers with one set blind rams and one set pipe rams. See attached exhibit.
------------	--

12. Mud Program:

N/A