

8 5/8" casing installation: 11"-5M BOP stack to be installed and tested by Yellow Jacket, Inc. to 3,000 psi before drilling the 8 5/8" casing shoe by Yellow Jacket, Inc. The BOP stack to consist of an annular BOP, blind ram BOP and one pipe ram BOP.

11. See Form 9-331C.
12. A. DST Program: (1) Bone Spring, (1) Wolfcamp
B. Core: None
C. Mud Logging: Two Man Unit 2920-TD
D. Wire Line Logs:

The following suite of logs will be run in both of the listed intervals:

- | | |
|---------------------------|---------------------------|
| Open hole: GR/CNL/Density | TD-2920' (GR-CNL to surf) |
| GR/Dual Laterolog-MSFL | TD-2920' |
13. No abnormal pressures anticipated with bottom hole pressures at TD expected to be 4500 psi. Bottom hole temperature 167° F. No Hydrogen Sulfide expected in this known drilling area. No crooked hole or abnormal deviation problems.
 14. Anticipated starting date to spud - on or before 2-19-86. Anticipated drilling time expected to be 33 days from surface to TD.

C. Nokes
1/30/86

RECEIVED

MAR 12 1986

C.C.D.
HOBBS OFFICE