

THYME "APY" FEDERAL #12
Page 3

7. Abnormal Conditions, Bottom hole pressure and potential hazards:
Anticipated BHP:
- | | | | |
|------------|----------|----------------------------|-----|
| From: 0 | TO: 1270 | Anticipated Max. BHP: 250 | PSI |
| From: 1270 | TO: 4810 | Anticipated Max. BHP: 2062 | PSI |
| From: 4810 | TO: TD | Anticipated Max. BHP: 3800 | PSI |

Abnormal Pressures Anticipated: None

Lost Circulation zones anticipated: None

H2S Zones Anticipated: None

Maximum Bottom Hole Temperature: 140°F

8. ANTICIPATED STARTING DATE:

Plans are to drill this well as soon as possible after receiving approval. It should take approximately 15 days to drill the well with completion taking another 20 days.