

No. 116 Langlie Jal Unit

7. AUXILIARY EQUIPMENT:

Equipment will include a gas detector, pit level monitor and a full-opening safety valve.

8. TESTING, LOGGING AND CORING PROGRAM:

Samples: Samples will be caught at 10' intervals from below the surface casing to total depth.

DST and Cores: None anticipated

Logging: Density-Neutron Log, Gamma Ray-Neutron Log

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE:

No abnormal pressure or temperatures anticipated. Precautions will be taken to monitor possible traces of hydrogen sulfide gas in the Grayburg. See H2S Plan attachment.

10. ANTICIPATED STARTING DATE:

Drilling will commence upon Federal and State approval. Drilling and completion will require about 30 days. Drilling contractor is available to start on July 16, 2001.